

The responses to bidders' inquiries are provided for the bidders' convenience only. In some instances, the question and answer may represent a summary of the matters discussed rather than a word-for-word recitation. The responses may be considered along with all other information furnished to prospective bidders for the purpose of bidding on the project. The availability or use of information provided in the responses to contractors' inquiries is not to be construed in any way as a waiver of the provisions of Section 2-1.03 of the Standard Specifications or any other provision of the contract, the plans, Standard Specifications or Special Provisions, nor to excuse the contractor from full compliance with those contract requirements. Bidders are cautioned that subsequent responses or contract addenda may affect or vary a response previously given. Inquiries along with responses may be posted at the website only when the inquiries are submitted in any of the acceptable manner prescribed under the Notice to the Contractors and when the responses have already been communicated to the individual inquirers. Bidders' inquiries received over the phone must be followed-up and submitted in writing for an official response.

The Bidders' inquiries and Responses may be updated from time to time and bidders are enjoined to check the website regularly and immediately prior to the scheduled bid opening.

Caltrans District 8 Office is located at 464 W. Fourth Street, San Bernardino, CA 92401-1400.

Send Contractor Inquiries via email to [d8\\_pbi@dot.ca.gov](mailto:d8_pbi@dot.ca.gov)

The mailing address is 655 2<sup>nd</sup> Street, San Bernardino, CA 92402.

Phone (909) 383-5961

Fax (909) 383-6739.

**All inquiries must include the contract number.**

08-0K7904	
Inquiry No.	Inquiry/Response
1.0	<p>Question_1: PLAN SHEET NO. 3 TYPICAL SECTION LOCALIZED DIG-OUTS INDICATES A 4' CONSTANT WIDTH. PLAN SHEET NO. 5 Q-1 1ST LOCATION BEGIN PM 12.00 END PM 12.06 NB DIRECTION AREA 3600(SQFT)WHEN DIVIDED BY .06 OF A MILE IN LENGTH EQUALS A WIDTH OF 11.36'. ALL SF AREAS INDICATED ON Q-1 ARE IN EXCESS OF A CONSTANT 4'. BASE UPON THE INFORMATION GIVEN CALCULATIONS SHOW AT LEAST 12' WIDTH. WHAT IS THE CORRECT CORRELATION?</p> <p><b>Response: The total width at each dig-out location will be in increments of 4' and up to 12'. The localized dig-outs (in 4' width) shown on the Construction Details (Plan C-1) is a dig-out increment of construction. They can dig out at a width of 12' at one time if needed or dig out at one increment and shift next increment at some distance along longitudinal direction based on the actual onsite condition.</b></p>
2.0	<p>Question_2: Construction detail indicates 4 foot wide localized dig-outs. The summary of quantities, length and cubic yards calculate much wider dig-outs. How wide are the Dig-outs?</p> <p><b>Response: Refer to the answer in Question #1</b></p>
3.0	<p>Question_3: Bid item No.4 Temporary Silt Fence 500 LF where is it to be installed (not shown on plans)?</p> <p><b>Response: The RE with the help from the biologist will direct the exact location to install Temporary Silt Fence prior to construction.</b></p>
4.0	<p>Question_4: Summary of Quantities indicates 500 LF of Temporary Fence (Type Wildlife) how is it to be paid? Where is it to be installed?</p> <p><b>Response: Temporary Fence (Wildlife) is to be paid by Temporary Silt Fence (Item Code 074029).</b></p>